

HDR


HDR Engineering, Inc.

ISSUE	DATE	DESCRIPTION

PROJECT MANAGER	R. HUFFMEYER
PROJECT NUMBER	240563


**HWR
GOFF STORAGE SYSTEM
NORWICH, OH**

**CIVIL
EROSION AND SEDIMENTATION
CONTROL PLAN**



FILENAME	00C-01.DWG
SCALE	AS SHOWN

SHEET
00C-01



ISSUE	DATE	DESCRIPTION

PROJECT MANAGER	—
PROJECT NUMBER	240563



**HWR
GOFF STORAGE SYSTEM
NORWICH, OH**

**GENERAL
GENERAL ARRANGEMENT**

012

12

2

FILENAME00G-01.DWG

SCALE1/8"=1'-0"



SHEET

00G-01

12345678

60'-0" 6 to 74'-0"

PLAN SCALE: 1/8"=1'-0"



- NOTES:
- SEE DWG. 00S-01 FOR STANDARD NOTES AND DETAILS.
 - SEE DWG. 00S-02 FOR CONCRETE KEY PLAN.

- LEGEND
- 3/2"x5/8" HEAVY DUTY GALVANIZED STEEL GRATING, TYPE WC BY HARSCO INDUSTRIAL IKG PRODUCTS OR EQUAL.
 - 2" FRP GRATING, DURADEK T-5000 (OR EQUAL). PROVIDE NON-SLIP SURFACE AND UV INHIBITOR.
 - PROVIDE A 4" WIDE x 4" HIGH CONCRETE CURB AROUND TWO SIDES OF THE PRECAST SUMP. DRILL AND GROUT CURB TO TOP OF PRECAST SUMP WALL.
 - PRECAST OR CAST-IN-PLACE CONCRETE SUMP. SEE CONCRETE NOTES ON DWG. 00S-01. PROVIDE BITUMINOUS COATING ON INTERIOR OF SUMP. FOR CIP SUMP, WALL AND SLAB THICKNESS = 8". REINFORCE WITH #5@9" FOR ALL WALLS AND SLAB, REBAR PLACED AT CENTER OF WALL OR SLAB.
 - 4" HIGH PAD (NOMINAL). T/PAD EL. 0'-3". SEE STANDARD HOUSEKEEPING PAD DETAIL ON DWG. 00S-01. PROVIDE A TROWEL FINISH.
 - PROVIDE A BROOM FINISH ON TRUCK UNLOADING PAD SURFACE. SEE CONCRETE NOTES ON DWG. 00S-01.
 - WHERE REINFORCING SPACING CHANGES, LAP REBAR AS REQUIRED, PER NOTES ON DWG. 00S-01.




ISSUE	DATE	DESCRIPTION
-------	------	-------------

PROJECT MANAGER	—
PROJECT NUMBER	240563

HWR
GOFF STORAGE SYSTEM
NORWICH, OH

STRUCTURAL
EXTENDED TRUCK UNLOADING AREA
ENLARGED CONCRETE PLAN AND SECTION



FILENAME	00S-02.DWG
SCALE	AS SHOWN

SHEET
00S-02